



2019 ANNUAL REPORT



G | W | R | S

GROUNDWATER REPLENISHMENT SYSTEM



SINCE 1933

Groundwater Replenishment System 2019 Annual Report



Prepared for the
California Regional Water Quality Control Board, Santa Ana Region
Order No. R8-2004-0002, as amended by
Order Nos. R8-2008-0058, R8-2014-0054, R8-2016-0051 and R8-2019-0007

by
Debra L. Burris, P.E.
Board Certified Environmental Engineer, American Academy of Environmental Engineers

DDB
ENGINEERING, INC.

1 Cavalier
Laguna Niguel, CA 92677
(949) 400-8575

June 19, 2020



TABLE OF CONTENTS

	<i>PAGE</i>
EXECUTIVE SUMMARY	ES-1
1. INTRODUCTION	
1.1. Purpose of the Annual Report	1-1
1.2. Groundwater Replenishment System	1-2
1.3. Talbert Barrier	1-9
1.4. Kraemer-Miller-Miraloma-La Palma Basins	1-12
1.5. Demonstration Mid-Basin Injection Project	1-18
1.6. History of OCWD Water Recycling Facilities	1-20
1.7. Water Recycling Permit Requirements	1-24
1.8. Operation Optimization Plan Overview	1-30
2. ADVANCED WATER PURIFICATION FACILITY PERFORMANCE	
2.1. Purified Recycled Water Volume and Flows	2-1
2.2. Purified Recycled Water Quality	2-2
2.3. Performance and Compliance Record	2-29
2.4. Santa Ana River Discharges	2-52
2.5. Anticipated Changes	2-54
3. TALBERT BARRIER OPERATIONS	
3.1. Barrier Injection Facilities	3-1
3.2. Injection Water Sources	3-1
3.3. Injection Water Volumes and Flow Rates	3-5
3.4. Barrier Operations	3-11



4. GROUNDWATER MONITORING AT THE TALBERT BARRIER

4.1. Talbert Gap Aquifers..... 4-1

4.2. Groundwater Monitoring Program 4-5

4.3. Groundwater Elevations and Directions of Flow..... 4-5

4.4. Groundwater Quality..... 4-24

5. KRAEMER-MILLER-MIRALOMA-LA PALMA BASINS OPERATIONS

5.1. Spreading Facilities 5-1

5.2. Spreading Water Sources 5-4

5.3. Spreading Water Volumes and Flow Rates 5-4

5.4. K-M-M-L Basins Operations..... 5-12

6. GROUNDWATER MONITORING AT THE ANAHEIM FOREBAY

6.1. Anaheim Forebay Aquifer System 6-1

6.2. Groundwater Monitoring Program 6-2

6.3. Groundwater Elevations and Directions of Flow..... 6-4

6.4. Groundwater Quality..... 6-14

7. DMBI PROJECT OPERATIONS

7.1. DMBI Injection Water Source 7-3

7.2. Injection Water Volumes and Flow Rates 7-3

7.3. DMBI Project Operations 7-5

7.4. MBI Centennial Park Project..... 7-10

8. GROUNDWATER MONITORING AT THE DMBI PROJECT

8.1. Aquifers in the DMBI Project Area 8-1

8.2. Groundwater Monitoring Program 8-6



	<i>PAGE</i>
8.3. Groundwater Elevations and Directions of Flow.....	8-6
8.4. Groundwater Quality.....	8-12

FIGURES

Figure ES-1	Groundwater Replenishment System Location Map.....	ES-2
Figure ES-2	2019 Purified Recycled Water Volume	ES-4
Figure ES-3	2019 Average Daily Purified Recycled Water Flow by Month	ES-4
Figure ES-4	Historical GWRS Purified Recycled Water Production Since 2008	ES-5
Figure 1-1	Groundwater Replenishment System Location Map.....	1-3
Figure 1-2	Groundwater Replenishment System	1-6
Figure 1-3	GWRS AWPf Process Flow Diagram.....	1-7
Figure 1-4	AWPF Site Layout	1-8
Figure 1-5	GWRS AWPf, Talbert Barrier and DMBI Project Location Map.....	1-10
Figure 1-6	Surface Water Recharge Facilities.....	1-13
Figure 1-7	Selected Forebay Monitoring and Production Well Locations	1-17
Figure 1-8	DMBI Project Location Map	1-19
Figure 1-9	Water Factory 21 in 1976.....	1-21
Figure 1-10	Interim Water Factory 21 in 2006.....	1-22
Figure 1-11	Philip L. Anthony Water Quality Laboratory	1-26
Figure 2-1	2019 Purified Recycled Water Volume	2-1
Figure 2-2	2019 Average Daily Purified Recycled Water Flow by Month	2-3
Figure 2-3	AWPF Process Sampling Locations Diagram	2-4
Figure 2-4	Secondary Effluent Flow Equalization (SEFE) Tanks and Pump Station.....	2-9
Figure 2-5	2019 AWPf Average Influent Flow Sources and Volumes.....	2-10



	<i>PAGE</i>
Figure 2-6	2019 AWPf Influent Sources and Average Flows by Month..... 2-11
Figure 2-7	MF System 2-12
Figure 2-8	2019 MF Turbidity Removal Performance 2-14
Figure 2-9	RO System..... 2-15
Figure 2-10	2019 RO Electrical Conductivity Removal Performance 2-17
Figure 2-11	2019 RO Total Organic Carbon Removal Performance 2-17
Figure 2-12	UV/AOP System 2-19
Figure 2-13	2019 UV/AOP NDMA Removal Performance 2-20
Figure 2-14	2019 RO/UV/AOP 1,4-Dioxane Removal Performance 2-23
Figure 2-15	Decarbonation System 2-24
Figure 2-16	Lime Post-Treatment System 2-25
Figure 2-17	Barrier and Product Water Pump Stations..... 2-25
Figure 2-18	2019 AWPf Total Nitrogen Removal Performance 2-27
Figure 2-19	2019 Purified Recycled Water Total Nitrogen..... 2-28
Figure 2-20	2019 Purified Recycled Water Total Organic Carbon..... 2-30
Figure 2-21	MF Log Reduction Values in 2019: <i>Giardia</i> Cysts and <i>Cryptosporidium</i> Oocysts (Minimum Daily Average of All 36 MF Cells) 2-40
Figure 2-22	TOC Reduction Achieved by the RO Process in 2019 2-44
Figure 2-23	RO Log Reduction Values in 2019: <i>Giardia</i> Cysts, <i>Cryptosporidium</i> Oocysts and Virus..... 2-45
Figure 2-24	UV/AOP Log Reduction Values in 2019: <i>Giardia</i> Cysts, <i>Cryptosporidium</i> Oocysts and Virus..... 2-48
Figure 2-25	Summary of Minimum Daily GWRS Pathogen Log Reduction Credits Achieved in 2019 2-51
Figure 3-1	Typical Legacy Injection Well 3-3
Figure 3-2	Typical Modern Cluster-Type Injection Well..... 3-3



	<i>PAGE</i>
Figure 3-3 Modern Injection Well Site I-26	3-4
Figure 3-4 2019 Talbert Barrier Injection Water Sources: Volumes and Flow Rates.....	3-5
Figure 3-5 2019 Monthly Injection Water Quantity at Talbert Barrier	3-7
Figure 3-6 Historical Injection Water Quantity at Talbert Barrier.....	3-10
Figure 3-7 2019 Talbert Barrier Monthly Injection Quantity by Aquifer Zone.....	3-14
Figure 3-8 2018 and 2019 Annual Average Injection Percentages for Each Depth Zone	3-15
Figure 3-9 2019 Talbert Barrier Injection Quantity at Each Well Site	3-18
Figure 4-1 Talbert Gap Study Area and Well Location Map	4-2
Figure 4-2 Schematic Geological Cross Section Through Talbert Gap	4-4
Figure 4-3 Shallow Aquifer Potentiometric Surface with Inferred Groundwater Flow Directions in the Talbert Gap Area During 2019	4-7
Figure 4-4 Talbert Barrier Injection, Coastal Production, and M26 Groundwater Levels....	4-10
Figure 4-5 Lambda Aquifer Potentiometric Surface with Inferred Groundwater Flow Directions in the Talbert Gap Area.....	4-13
Figure 4-6 Principal Aquifer Potentiometric Surface with Inferred Groundwater Flow Directions in the Talbert Gap Area.....	4-15
Figure 4-7 Monitoring Well OCWD-M10 Piezometric Elevations and Chloride Concentration.....	4-17
Figure 4-8 Monitoring Well OCWD-M11 Piezometric Elevations and Chloride Concentration.....	4-18
Figure 4-9 Monitoring Well OCWD-M19 Piezometric Elevations and Chloride Concentration.....	4-19
Figure 4-10 Monitoring Well OCWD-M45 Piezometric Elevations and Chloride Concentration.....	4-20
Figure 4-11 Monitoring Well OCWD-M46 and -M46A Piezometric Elevations and Chloride Concentration.....	4-21



	<i>PAGE</i>
Figure 4-12 Monitoring Well OCWD-M47 Piezometric Elevations and Chloride Concentration.....	4-22
Figure 4-13 Talbert Barrier Injection Water 1,4 Dioxane and NDMA Concentrations.....	4-31
Figure 4-14 Monitoring Well OCWD-M10 1,4-Dioxane and NDMA Concentrations	4-32
Figure 4-15 Monitoring Well OCWD-M11 1,4-Dioxane and NDMA Concentrations	4-33
Figure 4-16 Monitoring Well OCWD-M19 1,4-Dioxane and NDMA Concentrations	4-34
Figure 4-17 Monitoring Well OCWD-M45 1,4-Dioxane and NDMA Concentrations	4-35
Figure 4-18 Monitoring Well OCWD-M46 1,4-Dioxane and NDMA Concentrations	4-36
Figure 4-19 Monitoring Well OCWD-M47 1,4-Dioxane and NDMA Concentrations	4-37
Figure 4-20 MCWD-5 Pre-Treatment and Injection Water 1,4-Dioxane and NDMA Concentrations	4-45
Figure 5-1 Miller Basin with GWRS Purified Recycled Water in 2008.....	5-2
Figure 5-2 Miraloma Basin with GWRS Purified Recycled Water in 2012.....	5-3
Figure 5-3 La Palma Basin with GWRS Purified Recycled Water in 2016.....	5-3
Figure 5-4 2019 Spreading Water Sources and Volumes in Anaheim Lake/Mini-Anaheim Lake/K-M-M-L/La Jolla Basins	5-9
Figure 5-5 Spreading Water Sources and Volumes Since 2008	5-10
Figure 5-6 2019 Purified Recycled Water Spreading Operations.....	5-14
Figure 6-1 Selected Forebay Monitoring Well Locations and Buffer Areas	6-3
Figure 6-2 Generalized Geologic Cross Section in the Anaheim Forebay	6-5
Figure 6-3 Shallow Aquifer Groundwater Elevation Contours and Inferred Groundwater Flow Directions in the Anaheim Forebay Area	6-6
Figure 6-4 Monitoring Well OCWD-KB1 Piezometric Elevations and Chloride Concentration.....	6-8
Figure 6-5 Monitoring Well AMD-10 Piezometric Elevations and Chloride Concentration...	6-9
Figure 6-6 Monitoring Well AM-7 Piezometric Elevations and Chloride Concentration	6-10



	<i>PAGE</i>
Figure 6-7 Monitoring Well AMD-12 Piezometric Elevations and Chloride Concentration.....	6-11
Figure 6-8 Monitoring Well AM-8 Piezometric Elevations and Chloride Concentration	6-12
Figure 6-9 Monitoring Well AM-10 Piezometric Elevations and Chloride Concentration ...	6-13
Figure 6-10 Monitoring Wells AM-7 and AM-8 Total Arsenic Concentrations	6-23
Figure 6-11 Monitoring Well AMD-10 Total Arsenic Concentrations	6-24
Figure 6-12 Monitoring Well AMD-12 Total Arsenic Concentrations	6-25
Figure 6-13 Monitoring Well AMD-10/1 Chloride and Dissolved Arsenic Concentrations....	6-27
Figure 6-14 Monitoring Well AM-7 Chloride and Dissolved Arsenic Concentrations	6-28
Figure 7-1 Injection Well MBI-1 As-Built Construction Diagram.....	7-2
Figure 7-2 2019 Monthly Injection and Backwash Quantities at DMBI Project	7-4
Figure 7-3 2019 MBI-1 Injection Performance	7-5
Figure 7-4 2019 MBI-1 Pumping Performance	7-8
Figure 7-5 DMBI Project and MBI Centennial Park Project Location Map.....	7-12
Figure 8-1 DMBI Project Area and Well Location Map.....	8-2
Figure 8-2 Schematic Geological Cross Section Through the DMBI Project Area	8-4
Figure 8-3 Principal Aquifer Potentiometric Surface with Inferred Groundwater Flow Directions in the DMBI Area.....	8-8
Figure 8-4 Monitoring Well SAR-10 Piezometric Elevations and Chloride Concentration...	8-10
Figure 8-5 Monitoring Well SAR-11 Piezometric Elevations and Chloride Concentration...	8-11
Figure 8-6 Monitoring Well SAR-10 Chloride and Sulfate Concentrations	8-15
Figure 8-7 Monitoring Well SAR-11 Chloride and Sulfate Concentrations	8-16
Figure 8-8 Monitoring Well SAR-10 1,4-Dioxane and NDMA Concentrations	8-18
Figure 8-9 Monitoring Well SAR-11 1,4-Dioxane and NDMA Concentrations	8-19
Figure 8-10 Monitoring Well SAR-10 Chloride and Dissolved Arsenic Concentrations	8-21



	<i>PAGE</i>
Figure 8-11	Monitoring Well SAR-11 Chloride and Dissolved Arsenic Concentrations 8-22
Figure 8-12	Monitoring Well SAR-10 Chloride and Dissolved Vanadium Concentrations..... 8-26
Figure 8-13	Monitoring Well SAR-11 Chloride and Dissolved Vanadium Concentrations..... 8-27
Figure 8-14	Monitoring Wells SAR-10 and SAR-11 Total and Dissolved Aluminum Concentrations 8-30
Figure 8-15	Wells IRWD-12 and IRWD-17 Chloride and Sulfate Concentrations..... 8-33

TABLES

Table ES-1	2019 Summary of Purified Recycled Water Flows and Discharge Points ES-3
Table ES-2	2019 Average Purified Recycled Water Quality ES-6
Table ES-3	Summary of GWRS Minimum Pathogen Log Reduction Credits Achieved in 2019 ES-6
Table ES-4	2019 GWRS Injection at the Talbert Barrier..... ES-7
Table ES-5	2019 GWRS Spreading in the Vicinity of Kraemer-Miller-Miraloma-La Palma Basins ES-9
Table 1-1	2019 Summary of Purified Recycled Water Flows and Discharge Points 1-4
Table 1-2	Summary of GWRS Purified Recycled Water Quality and Monitoring Requirements 1-27
Table 1-3	GWRS Independent Advisory Panel 1-30
Table 2-1	2019 Average Water Quality 2-6
Table 2-2	Comparison Between 2018 and 2019 Average Water Quality 2-7
Table 2-3	2019 MF Performance..... 2-14
Table 2-4	2019 RO Performance 2-16
Table 2-5	2019 UV/AOP NDMA Removal Performance 2-20
Table 2-6	2019 RO/UV/AOP 1,4-Dioxane Removal Performance..... 2-23



	<i>PAGE</i>
Table 2-7	2019 AWPf Total Nitrogen Removal Performance 2-27
Table 2-8	Summary of Critical Control Points and Critical Limits..... 2-33
Table 2-9	RO System Membranes 2-42
Table 2-10	Summary of GWRS Minimum Pathogen Log Reduction Credits Achieved in 2019 2-50
Table 2-11	Summary of CEC and Surrogate Monitoring for GWRS in 2019..... 2-53
Table 3-1	Talbert Barrier Injection Well Design Criteria 3-2
Table 3-2	2019 Monthly Injection Water Quantity at Talbert Barrier 3-6
Table 3-3	Historical Injection Water Quantity at Talbert Barrier..... 3-9
Table 3-4	2019 Injection Quantity at Talbert Barrier Well Sites 3-17
Table 3-5	2019 Injection Wells Operational Status..... 3-20
Table 4-1	2019 Water Quality for Potable and Non-Potable Wells Within the Influence of the Talbert Barrier 4-43
Table 5-1	Area and Storage Capacities of Recharge Facilities 5-1
Table 5-2	2019 Summary of Spreading Water Locations and Volumes..... 5-6
Table 5-3	2019 Summary of Spreading Water Sources and Quantities..... 5-7
Table 5-4	Summary of Spreading Water Sources and Volumes Since 2008 in the Anaheim Forebay 5-11
Table 5-5	2019 Purified Recycled Water Spreading Volumes and Flow Rates 5-13
Table 6-1	Approximate Aquifer System Depths in the Vicinity of K-M-M-L Basins 6-2
Table 6-2	2019 Water Quality for Potable Well Within the Influence of K-M-M-L Basins . 6-32
Table 7-1	2019 Monthly Injection and Backwash Quantities at DMBI Project..... 7-3
Table 8-1	Approximate Aquifer System Depths in the DMBI Project Area..... 8-3
Table 8-2	GWRS Water Arrival Time Estimates from MBI-1 to SAR-10 and SAR-11..... 8-14
Table 8-3	2019 Water Quality for Potable Wells Within the Influence of the DMBI Project 8-31



ACRONYMS

Acronyms ListL-1

REFERENCES

References R-1

APPENDICES

Appendix A – Water Quality Requirements for Groundwater Replenishment System and Final Product Water Quality Data, January 1 through December 31, 2019

Appendix B – Laboratory Methods of Analysis

Appendix C – Water Quality Constituents with Laboratory Methods

Appendix D – Operator Certifications, Operations and Maintenance Summary and Calibration Records

Appendix E – Critical Control Points

Appendix F – Pathogen Log Reduction Value (LRV) Reports

Appendix G – Groundwater Quality Data at the Talbert Barrier

Appendix H – Talbert Barrier Monitoring Well Groundwater Quality Data, 1,4-Dioxane, NDMA and Selected Constituents

Appendix I – Groundwater Quality Data at the Anaheim Forebay

Appendix J – Anaheim Forebay Monitoring Well Groundwater Quality Data, 1,4-Dioxane, NDMA and Selected Constituents

Appendix K - Groundwater Quality Data at the Mid-Basin Area

Appendix L - Mid-Basin Injection Area Monitoring Well Groundwater Quality Data, 1,4-Dioxane, NDMA and Selected Constituents

Cover photo courtesy of OCWD - GWRS Final Expansion construction in the MF area in May 2020.